Dated 31st October 1933.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 2 P.M. on 20th November 1933, for the work of restoring Vanigānahalli, Mallukunte tank, Sl. No. 148 of Mulbagal Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1935.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar, between the hours of 2 P.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tender should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees three hundred (Rs. 300) in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for the work of restoring Vaniganahalli Mallukunte tank R. No. of Mulbagal Taluk in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office, in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. The rates should be entered in words and figures. Petitions praying for the adjustment of earnest money out of the amounts of bills pending payment will be summarily rejected.

Abstract estimate for Restoring Vaniganahalli Mallukunte tank Mulbagal Taluk.

No.	Items of work	Unit	Rate	Quantity	Cost
	Bund.		Rs. a. p.		Rs.
1	Clearing thick Nagadlali jungle ...	Grades	2 0 0	19	38
2	Cutting big trees on bund including removing roots.	No.	1 0 0	20	20
3	Removing ant hills and filling with sand.	No.	1 0 0	20	20
4	Cutting grips $\frac{3' \times 3'}{2}$ to bund ..	Grades	2 0 0	19	38
5	Earthwork to bund with watering and tamping.	C.yds.	0 3 0	7,992	1,748
6	Clearing silt	„	0 2 6	22	3
7	Turfing both slopes	Syds.	0 1 0	6,073	380
8	Resetting old stone work with new jelly.	C.yds.	0 12 0	463	347
9	Rough stone work new with pitching abake 50·00 to 53·00.	...	1 8 0	1,126	1,689
10	Providing grade stones with index stones, complete.	No.	2 0 0	22	44
11	Providing B. M. stones complete ...	„	2 8 0	2	5
12	Providing date and Regd. No. stones complete.	„	2 8 0	2	5
13	Providing Gauge stone complete ...	„	12 0 0	1	12
	Total ...	..	.....	..	4,349

No.	Items of work	Unit	Rate	Quantity	Cost
	Sluice.		Rs. a. p.		Rs.
1	Earthwork cutting open the bund ...	C.yds.	0 3 0	45	8
2	Stone jelly concrete in surki mortar ..	C.ft.	0 4 0	345	86
3	Burnt brick in surki mortar ...	„	0 4 6	264	74
3a	Do stone do ..	...	...	..	...
4	Burnt stone slabs 4″ to 6″ thick dressed.	S.ft.	0 6 0	228	86
5	Plastering with surki mortar ...	Sqr.	4 0 0	4·76	19
5a	Pointing with cement mortar ...	...	..	...	..
6	Cutting holes for orifice in slabs and top slab of gibbet.	No.	1 0 0	3	3
7	Providing angle iron rod 2″ x 2″ and plug with locking arrangements complete.	„	12 0 0	1	12
8	Dismantling old damaged tunnel ..	Lump	Sum	..	20
9	Earthwork refilling the bund with watering and tamping.	C.yds.	0 3 0	50	9
	Total for Sluice ...	...	...	..	317
	Left Waste Weir.				
1	Earthwork excavation	C.yds.	0 3 0	169	32
2	Stone jelly concrete in Surki mortar ..	C.ft.	0 4 0	423	106
3	Burnt brick in surki mortar or. . ..	„	0 4 6	687	193
3a	Burnt stone in surki mortar ...	..	...	..	...
4	Burnt stone slabs 6″ thick dressed ..	Sft.	0 6 0	436	163
5	Cutting joggles	each	1 0 0	20	20
6	Plastering with surki mortar or ..	Sqr.	4 0 0	7·57	30
6a	Pointing with cement mortar ...	...	...	...	..
7	Row stonework new	C.yds.	1 8 0	99	148
	Total ...	....	..	...	692
	Right Waste Weir.				
1	Earthwork excavation ..	C.yds.	0 3 0	76	14
2	Stone jelly concrete in surki mortar ...	C.ft.	0 4 0	370	92
3	Burnt brick in surki mortar or ..	„	0 4 6	609	171
3a	Stone in surki mortar ..	..	...	...	..
4	Burnt stone slabs 6″ thick dressed ..	S.ft.	0 6 0	312	117
5	Cutting joggles	each	1 0 0	16	16
6	Plastering with surki mortar or ...	Sqr.	4 0 0	6·75	27
6a	Pointing with cement mortar ..	...	...	...	...
7	Rough stone work new	C.yds.	1 8 0	61	91
	Total ...	...	...	...	528

Total 4349+317+692+528=Rs. 5,886.

Dated 28th October 1933.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 2 P.M. on 20th November 1933, for the work of Restoring Venkatapur Melinakere R. No. 133 of Sidlaghatta Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1934.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar between the hours of 2 P.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 190 in cash or Government Promissory Notes, as earnest money and be superscribed "Tender for the work of Restoring Venkatapur Melinakere R. No. 133 of Sidlaghatta Taluk" in default of which, tenders will be rejected.

5. The final acceptance of any tender, will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor whose tender has been accepted will be posted on the Notice Board of the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. The rates should be both in figures and words. The earnest money should be in cash. Petitions praying for adjusting the earnest money out of the amount of bills pending payment will be summarily rejected.

Abstract estimate for Restoring Venkatapur Melinkere *alias* Thipparajakere, Sadli Hobli, Regd. No. 133 of Sidlaghatta Taluk.

No.	Items of work	Unit	Rate	Quantity	Cost
	Bund R. L. 56·00.		Rs. a. p.		Rs.
1	Earthwork to bund watering and tamping, etc.	C.yd.	0 3 6	3,720	814
2	Turfing to bund ...	S.yd.	0 1 0	2,328	146
3	Revetting old stone revetment with required new jelly.	C.yd.	0 12 0	163	122
4	New stone revetment with jelly backing and wedging.	,,	1 12 0	700	1,225
5	Grade stone including zero stone cutting figures, painting and fixing, etc.	Each	1 8 0	6	9
6	Index do do ...	,,	0 8 0	6	3
7	B. M. stones do do ...	,,	2 0 0	2	4
8	Registered No. date stone do. ..	,,	5 0 0	1	5
9	Gauge stone do do ...	,,	15 0 0	1	15
10	Removing top soil and cutting trenches 3' x 3½' to old bund grades.	Grade	4 0 0	5	20
	Total bund ...	...	..	..	2,363
	Waste Weir Left R. L. 50·00.				
1	Clearing weir site and removing boulders, etc.	Lump	sum	..	30
2	Excavation earthwork (hard soil) ...	C.yd.	0 5 0	16	5
3	Concrete in surki mortar ...	C.ft.	0 4 0	130	32
4	Burnt stone in surki mortar ..	,,	0 5 0	163	51
5	Burnt stone slabs 4" to 6" thick neatly dressed.	S.ft.	0 5 0	130	41
6	Pointing with cement ...	Sqr.	4 8 0	2·98	13
7	New stone work ...	C.yd.	1 12 0	19	33
8	Providing joggles ...	Each	0 8 0	4	2
9	Draft clearing and removing boulders in weir halla.	Lump	sum	...	30
10	Unforeseen charges lumpsum of rupees.	...	...	..	10
	Total waste weir left ..	..	..	...	247

No.	Items of work	Unit	Rate	Quantity	Cost
	Waste Weir Right R. L. 50·00.		Rs. a. p.		Rs.
1	Earthwork excavation hard soil mixed with jelly.	C.yd.	0 6 0	19	7
2	Concrete in surki mortar ...	C.ft.	0 4 0	215	54
3	Burnt stone in surki mortar or: ...				
3a	Burnt brick in surki mortar ...	„	0 5 0	309	97
4	Pointing with cement or surki plastering.	Sqr.	4 8 0	3·97	18
5	New stone work ...	C.yd.	1 12 0	41	72
6	Filling in jelly below apron ...	„	1 0 0	9	9
7	Burnt stone slabs 4" to 6" thick ...	S.ft.	0 5 0	151	47
8	Providing joggles ...	Each	0 8 0	6	3
9	Unforeseen items charges ...	Lump	sum	...	10
	Total Right Waste Weir ...	...	...	...	317
	Sluice R. L. 39·00.				
1	Earthwork excavation hard soil mixed with jelly.	C.yd.	0 6 0	112	42
2	Concrete in surki mortar ..	C.ft.	0 4 0	315	79
3	Burnt brick in surki mortar ...	„	0 4 6	1,337	376
4	Burnt stone slabs 4" to 6" thick, neatly dressed.	S.ft.	0 5 0	301	94
5	Drilling holes in slabs ...	Lump	sum		5
6	Plastering with surki mortar or ...				
6a	pointing with cement mortar.	Sqr.	4 0 0	11·81	47
7	Refilling the earth as per excavation ..	C.yd.	0 3 0	112	21
7a	Add ⅓ of gravel to be mixed for front slope.	„	0 8 0	34	17
8	Providing teak wooden plug with angle iron rod 2' x 2".	Each	20 0 0	1	20
9	Dismantling the old sluice and for forming approach and leading channels.	Lump	sum	....	20
	Total Sluice ...	...	...	...	721
	Total 2363+247+317+721= Rs. 3,648.	..	...	....	...

C. T. NARASIMHA IYENGAR,
Executive Engineer.

TUMKUR DIVISION.

Abstract Notification, dated 28th October 1933.

SUBJECT:—Restoring Besige Doddakere, Reg. No. 88 of Tiptur Taluk.

Attention of the public is drawn to the notification calling for tenders for the above work in pages 1368 and 1369, Part VI of the *Mysore Gazette*, dated 2nd November 1933.

2. Tenders will be received by the Executive Engineer, Tumkur Division, Tumkur, up to 2 P.M. of 27th November 1933.

3. An earnest money of Rs. 300 should accompany the tender.

Abstract Notification, dated 22nd October 1933.

SUBJECT:—Restoring the Breached Gowdihalli Tank R. No. 326 of Tumkur Taluk.

Attention of the public is drawn to notification, calling for tenders for the above work in pages 1367, and 1368, Part VI of the *Mysore Gazette*, dated 2nd November 1933.

The tenders will be received at the Office of the Executive Engineer, Tumkur Division, Tumkur, up to 2 P.M. of 27th November 1933.

3. An earnest money of Rs. 200 should accompany the tender.